



Schedule of Accreditation
for testing Laboratory According to ISO/IEC 17025

Water Pump Testing Laboratory

General Organization For Exports and Imports Control (GOEIC)
Ain El Sokhna Port Branch - Ain El Sokhna - Suez Governorate - Egypt

Schedule No.: 042310B 1st Accreditation Date: February 28, 2024 Issue No. (01): February 28, 2024 Revision No.(01): April 27, 2025 Valid to : February 27, 2028

Materials / Products Tested	Types of Tests / Properties Measured / Range of Measurements	Standard Specifications / Techniques Used
Water Pump	Performance Test of Guarantee point test for pump Flow rate: 15 L/min to 1200 L/min Head up to 150 m	ISO 9906/2012 ES 4104/2018 Water Pump Tester; MODEL: WP-1000 S.N.: 21566 Manufacturer: BTC LINE 1 (1) Flow Meter S.N: FA202B19000 Pressure Sensor S.N: 02040295 Vacuum Sensor S. N.: 10959505 LINE 2 (2) Flow Meter S.N: 6804B619000 Pressure Sensor S.N: 02340280 Vacuum Sensor S. N.: 11475134 LINE 3 (3) Flow Meter S.N: 8A124819000 Pressure Sensor S.N: 11470401 Vacuum Sensor S. N.: 10959513 LINE 4 (4) Flow Meter S.N: 5203CD91000 Pressure Sensor S.N: 11470400 Vacuum Sensor code NO.: WP10 LINE 5 (5) Flow Meter S.N: N90F7919000 Pressure Sensor S.N: 02040255 Vacuum Sensor S. N.: 10959496

Haide El Desouki Amin